

DURBAN'S GAS-TO-ELECTRICITY PROJECT



**BIOMASS WORKSHOP
DURBAN**

29 APRIL 2014


**John Parkin
Deputy Head: Plant & Engineering
eThekweni Municipality**

NATIONALGEOGRAPHIC.COM/MAGAZINE

SEPTEMBER 2004

NATIONAL GEOGRAPHIC GLOBAL WARNING

BULLETINS FROM A WARMER WORLD



The New Face of the American Indian 76 Badgers With Attitude 96
Treasure From a Civil War Wreck 108 ZipUSA: Schooled in Tradition 128
PLUS Supplement Map: Indian Country

DSW

PROOF OF GLOBAL WARMING



GAS PRODUCTION

“A rule-of-thumb is that 6 – 10m³ of landfill gas will be produced per ton of waste per year for 10 – 15 years from placement”

(Robert Eden, et al; 2002)


- Roughly $500\text{Nm}^3/\text{hr}$ from every 1m t of waste.
- 1MW electricity from every $700\text{Nm}^3/\text{hr}$ of gas





AFRICA'S FIRST LANDFILL GAS CDM PROJECT








copyright rickleeks.com



UNSUSPECTING & NAIVE




www.StrangeCosmos.com





CHAMPION PASSIONATE



BITTEN OFF MORE THAN WE COULD HANDLE



MARINNHILL LANDFILL



1 MW ENGINE



BISASAR ROAD LANDFILL



COMMISSIONED 6,5 MW JULY 2009





The CDM Project Process

- PIN
- PCN
- Conditional Approval from DNA (DoE)
- Base-Line Study
- Validation Report
- MP (Monitoring Plan)
- PDD (Project Design Document)
- Comment from Public and Stakeholders
- EIA Process and obtain ROD for Project
- Verification of Project
- Final DNA Approval
- Project Registration with CDM Exec Board

PROCESS LIKE A WOLF IN SHEEP'S CLOTHING



LFG-to-Elec CDM Project Time Frames

First contact with PCF/World Bank	November 2001
MOU between eThekweni and PCF –	February 2003
Commence EIA's –	July 2003
Adhoc Approval for funds –	October 2003
ROD's for Mariannhill and La Mercy (“Component One”) –	July 2004
Appeal against “Component One”	August 2004
Appeal response to Minister of DAEA for “Component One” –	September 2004

LFG-to-Elec CDM Project Time Frame Cont

ROD Bisasar (“Component Two”) –	October 2004
Started construction “Component One”	January 2006
Final Revised ROD for “Component Two” (Bisasar) –	August 2006
CDM Registration of Component 1 (Mariannhill & La Mercy) –	November 2006
Commissioning of Mariannhill & La Mercy Flares & Gens –	Nov~Dec 2006
Initial Verification of Mariannhill	January 2007

LFG-to-Elec CDM Project Time Frame Cont

“Component Two” (Bisasar) Start Construction –	March 2007
Verification of “Component 1” Year 1	January 2008
Commissioning of Bisasar Rd Flare & Engines	March 2008
Registration of Component 2 (Bisasar Rd)-	March 2009
Commissioning of 6,5 MW Component 2 (Bisasar Rd)	July 2009
Initial Verification Bisasar	November 2009
2nd Verification Mariannhill	November 2009

LFG-to-Elec CDM Project Time Frame Cont

3rd Verification Mariannhill	September 2011
First Issuance Bisasar (65 711)	30 December 2011
Sale of VCU's (124 884)	January 2012
Commission Gas Chiller	May 2012
First Issuance Mariannhill (39 472)	March 2013
4th & 2nd Verifications Mariannhill & Bisasar	March 2013
2nd , 3rd & 4th Issuance Mariannhill	May, June, Aug 2013

LFG-to-Elec CDM Project Time Frame Cont

Reregistration of Mariannhill Project (ACM 0001)

December 2013

2nd Issuance Bisasar (749 633)

February 2014

5th Verification Mariannhill

March 2014


Calculated Emission Reductions (in tons)

Site	Methane Destruction	Electricity Generation	TOTALS
Bisasar Road	5,295,296	800,704	6,096,000
Mariannhill	1,112,568	112,344	1,224,912
La Mercy	488,972	24,511	513,483
TOTALS	6,896,836	937,559	7,834,395

THE TEAM

- In House Project Management
- Legal Imbewu Environmental Legal Services
- Gas Specialist SLR Ltd (UK)
- Civil Consultants Wilson & Pass Inc.
- PCF World Bank
- DTI & DoE
- French Development Bank
- EIA Felehetsa / WSP Environmental
- External Verifiers (was SGS now DNV)
- CER Purchaser

WHEN THINGS GO WRONG




GAS CHILLER

- DROPPING OUT 95 l/hr







Lipinsky/Albion 12/100

DSW

ADMINISTRATIVE CHALLENGES

- MFMA & SCM don't deal with out of ordinary processes
- EIA Process was problematic
- Registration by UNFCCC Ex Board long, tedious & pedantic
- Inconsistent decisions by Ex Board
- No direct access to Ex Board (recent change)
- Monitoring Onerous, Expensive
- Language is often a barrier
- Drawn out process
- Whole process is costly
- DOE accreditation

TECHNICAL CHALLENGES

- Lack of Expertise & Resources
- Extreme weather conditions
- Excess leachate; poorly run site
- Manufacturers supplying incorrect equipment
- Lack of sharing information
- Lack of Experience / Technical Ability
- Understanding the Gas Field


OPERATING CHALLENGES

- Service Suppliers lack of Expertise
- Cost of Spares & Oil
- Cost of Services
- Availability of Spares
- Need good Quality Assurance
- Monitoring: correct procedures
- Logging of raw data & interpretation
- Verification

LEASONS LEARNED

- Be wary of “Experts”
- Easier to deal with Technical challenges than Political & Administrative issues
- Running of Landfill is as important as the Extraction Process
- Carry out a pre Verification Inspection, saves a lot of stress at verification but not time
- Add 12 months to any time frame given
- Cash flow is a major problem
- CER price has crashed (€15,07 vs 0,22/€0,31)

WE'RE STILL LEARNING



**GOOD WORK, BUT I THINK WE
MIGHT NEED JUST A LITTLE
MORE DETAIL RIGHT HERE**

FRUSTRATED




NO CONTROL



OUTWEIGHED



AH ST- - F IT



SHOW ME THE MONEY



Project Review

- The capital and operating expenditures of the project are supported by two revenue streams:
 - Sale of Carbon Credits
 - Sale of Electricity
- Without the sale of carbon credits, the project would not be financially viable.

ELECTRICITY SALES BISASAR

	UNITS	HIGH RATE	AMOUNT	LOW RATE	AMOUNT
PEAK	432480	190,00	821 712,00	61,97	268 007,86
STAND- ARD	1138080	57,56	655 078,85	42,66	485 504,93
OFF PEAK	1943920	31,25	607 475,00	27,06	526 024,75
SUR- CHARGE		10,05%	127 953,75		127 953,75
RURAL LEVY		5,17	181 698,62		181 698,62
TOTAL			2 393 918,22		1 589 189,91

ORIGINAL REFIT (92c) R 3 233 321



CURRENT STATS

- ❖ 7.5 MW Generation of Electricity Capacity
- ❖ Electricity Supply to 3 750 small houses
- ❖ Total LFG Flow ~ 4 400 Nm³/hr at 53% CH₄
- ❖ 20 000 Tons CO₂ equivalent destroyed /month
- ❖ 1,6m tons of CO₂ equivalent destroyed to date
- ❖ >R100m worth of electricity generated to date
- ❖ > 255 000 MWh generated
- ❖ >R3,4m electricity income in July 2012

CASH FLOW

INCOME

- **ELECTRICITY SALES**
R1 850 000 / month
- **CARBON CREDITS**
R1 000 000 / month
€5/CER
- **TOTAL**
R 34 000 000 / annum

EXPENDITURE

- **CAPITAL EXPENDITURE**
TO DATE R121 000 000
- **ANNUAL OPERATING**
R13 000 000

Concluding Comments

- Landfill gas offers a viable renewable energy source only when linked to Carbon Finance, CDM or ReBid (R0.72/kWh)
- VER's may be more viable than CER's due to over the top requirements of UNFCCC Process and price
- The EIA process has over-ripened this fruit – lost two years
- Lack of Technical Skills is restricting expansion in Africa
- Implementation of proven technologies is a must
- Distance from Europe is detrimental to fast reaction
- Exchange rate has a dramatic influence on cash flow

Six African projects named among world's 100 most innovative

By: Irma Venter

Published: 27 Aug 12







EXCEEDED EXPECTATION

DSW

HOPE THINGS ARE CLEARER



www.dbnlandfillgas2elec.co.za